

# Corrigendum -1

Date: 16.04.2026

**Limited RFP- Selection of System Integrator to provide O&M services of ETC System at Toll Plazas on National Highways**

**RFP No. IHMCL/LTE-RFP/ ETC-O&M/2026/05 dated 15.04.2026.**

**Following Corrigendum-1 is issued for abovementioned RFP:**

<b>SL#</b>	<b>RFP Reference</b>	<b>Original Clause</b>	<b>Amended Clause (To be read as)</b>
1	Part VII – ANNEXURES AND FORMS CLAUSE 7.11	Annexure-F - Deleted	Annexure-F – Compliance for Commencement of O&M services  Service Provider shall be required to submit compliance report as provided below upon start of O&M services at the fee plaza as per scope mentioned in the RFP.

## Annexure-F – Compliance for Commencement of O&M services

Lane Level Equipment					
S.No	Equipment Description	Lane 1	Lane 2	Lane 3	Lane...n
1	RFID ETC transceiver near Pay-axis – (mounted on canopy/Pole as per site feasibility)				
2	Lane Controller with Industrial PC				
3	AVC including sensors, Controller, loop and detector				
4	User Fare Display with mounting pole				
5	Automatic Barrier Gate				
6	Overhead Lane Status light (OHLS)				
7	Traffic light with mounting pole				
8	Loop with detector				
9	Incident Capture Camera/Lane Monitoring Camera with mounting pole				
10	TFT Monitor				
11	Customized industrial grade keyboard				
12	Thermal Receipt Printer				
13	Violation light & Alarm (on existing pole) and Foot switch in booth				
14	Booth CCTV camera with voice recording				
15	Intercom Slave unit in booth				
16	Lane Level UPS including Batteries				
17	Automatic Number-Plate Recognition Camera				
Plaza Level Equipment					
S.No	Equipment Name	Status			
1	ETC Server (Plaza)				
2	Workstations for MIS, Cashup, Audit & LSDU System (in control room)				
3	24 Port Network switch (Layer 3)				
4	Provision for Internet services (02 Qty) with static IP addresses, ensuring a minimum bandwidth equivalent to 02 Mbps per lane				
5	UPS system as required for complete ETC system (10 KVA or above) including Batteries				
6	Network Video Recorder (NVR) for CCTV (Booth Camera, Lane Monitoring Camera and Plaza Building Camera) recording with minimum 60 days of storage				
7	CCTV cameras for Plaza building surveillance (server room, control room, cash room, admin)				
8	Master Intercom System				
9	Servo Stabilizer (60 KVA -03 phase)				
10	Firewall Hardware				
Status of Supplied, Installation & Commissioning of Not Available Equipment					
S.No	Equipment Name	Qty	Status	Specification as per Contract Agreement(Yes/ No)	
1					
2					
S.No	General Checklist	Status			
1	ANPR Functionality in all lanes using existing LPIC Camera Camera				
2	ICD 2.5 migration				
3	Software Migration in Lane System and Plaza System				
4	Installation and commissioning of additional equipment				
5	Performance of RFID Reader i.e., Manual Transaction Count >10% of Total FASTag transaction				
6	AVC Accuracy >98% in all lanes				
7	Taking a complete backup of the database from the previous System Integrator and storing all fields of data in the system application by Service Provider				